

# Waste Pro Tanks

Aboveground Double Wall Used Oil Storage

**H.O.D., Inc.**

Environmentally-Friendly Solutions for  
Fleet and Equipment Maintenance  
Serving Government, Private & Utility Industries

CAN/ULC S-652-Latest Standard

## TTS Premium Series 2 Specification



\* 660 Gal. model shown

- Double wall construction, horizontally built
- Saddles fully welded
- 1/8" thick steel shell construction
- Interstice vacuum monitoring gauge with guard
- 2" male quick coupling in spill box
- 2" normal vent c/w cap
- Steel spill box cover with stainless steel hinges c/w splash guard
- Comes with Level Charts
- Check with installer and local jurisdiction for additional norms and regulations.

## Tank Exterior

- Sandblasted to SSPC-SP6, commercial blast
  - E2 Paint system :
    - Two part high built epoxy 4-6 mils dry
    - Two part Polyurethane epoxy 2-3 mils dry
  - Safety Labeling as per codes
  - Product Labeling on three sides
- \*Paint Warranty for TWO(2) years from date of manufacturing  
\*Tank Warranty for a period of FIVE(5) years from date of manufacturing

## Options

- 15 mil Interior Liner
- Pumping station
- Liquid level gauge
- Remote collection box
- Manway & spill box combo
- Solenoid switch on vacuum gauge

Model	Double Wall	Specifications					
		Dia.	OAL	Shell	Paint	Step	Fittings
132 G.	•	37.5"	30"	1/8"	Polyurethane epoxy finish	O	Two(2) N.P.T. 2"
264 G.	•	37.5"	60"	1/8"	Polyurethane epoxy finish	O	Two(2) N.P.T. 2"
396 G.	•	37.5"	84"	1/8"	Polyurethane epoxy finish	O	Two(2) N.P.T. 2"
528 G.	•	50.0"	60"	1/8"	Polyurethane epoxy finish	S	Two(2) N.P.T. 2"
610 G.	•	50.0"	72"	1/8"	Polyurethane epoxy finish	S	Two(2) N.P.T. 2"
725 G.	•	50.0"	84"	1/8"	Polyurethane epoxy finish	S	Two(2) N.P.T. 2"
1 180 G.	•	50.0"	144"	1/8"	Polyurethane epoxy finish	S	Two(2) N.P.T. 2"

**H.O.D., Inc.** 7 Badger Ave., Natick, MA 01760 Phone:1.508.650.1120 Fax:1.508.650.5358 [sales@hodinc.com](mailto:sales@hodinc.com)